

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No.EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE -'B'

Item-15

Name of Work:-Providing Street Ornamental and sign boards in kempegowda ward no-01

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates ~~80.7~~ Sri SATISH N	
				Rate	Rate in Words
1	Providing and fixing ornamental name boards of size 2.10 X 0.50Mtrs and column of size 0.15 x 0.15 Mtrs of height 1.23 Mtrs of each board made of C C 1:1, 5:3 with necessary centering and form work smooth finishing with reinforcement etc including fabrication charges painting concreting and transportation charges from manufacturing yard to the site of work all lead and lift loading and unloading and labour charges etc. complete as per the direction of the engineer incharge of the work ✓	Each	15.00	5784.60	Rupees Five Thousand Seven Hundred Eighty Four and Paise Sixty Only
2	Retro - Reflectorised Traffic Signs :- Providing and fixing of retro - reflectorised cautionary, mandatory and informatory sign as per IRC : 67 - 2001 made of high intensity grade micro prismatic HIP type IV sheeting, fixed over aluminium sheeting, 2mm thick firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cms x 45cm x 60cm, 60 cm below ground level as per approved drawing. The item includes earthwork excavation, Cement Concrete M15 grade, 2 coats of approved colour synthetic enamel painting to the steel surface, as per clauses, including curing, cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete.(P.No.65, I.No.8.04 of NH SR 2009-10) Supported on a class B GI pipe 80mm outer dia, 3.50mtr long 60cm x 60cm square ✓	Each	55.00	4539.42	Rupees Four Thousand Five Hundred Thirty Nine and Paise Forty Two Only
3	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 SR 2018-19 ✓	Cum	3.67	295.71	Rupees Two Hundred Ninety Five and Paise Seventy One Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates ~~300~~ Sri SATISH N	
				Rate	Rate in Words
4	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	Cum	3.67	81.69	Rupees Eighty One and Paise Sixty Nine Only
5	KSRB4.1.3: Providing and laying position plain cement concrete of Mix 1:4:8 with OPC cement @180Kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed , concrete laid in layers not exceeding 15 cms, thick, well compacted , in foundation , including cost of all materials, Labour , HOM of Machinery, Curing complete as per Specifications. Specifications No. KBS 4.1, 4.2 (P12/4.3). SR 2018-19	Cum	3.67	5045.78	Rupees Five Thousand Forty Five and Paise Seventy Eight Only
6	KSRRB 800-1: painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specification MORTH chapter 8, No. 180/ Item No. 24.1/ PWD SR 2018-19	Sqm	278.70	79.12	Rupees Seventy Nine and Paise Twelve Only
7	KSRRB M800-9: Painting new Kannada letter and figures of any shade with synthetic enamel paint block or any other approved colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) MORTH specification No. 803, No. 181/ Item No. 24.9/ PWD SR 2018-19	Cm	38000.00	0.99	Rupees and Paise Ninety Nine Only

Satish N
Signature of the Contractor

[Signature]
Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64